

Electronic properties of alkali-metal loaded zeolites — a “supercrystal” Mott insulator

Ryotaro Arita¹, Takashi Miyake², Takao Kotani³, Mark van Schilfgaarde⁴, Takashi Oka¹, Kazuhiko Kuroki⁵,
Yasuo Nozue³ and Hideo Aoki¹

¹*Department of Physics, University of Tokyo, Hongo, Tokyo 113-0033, Japan*

²*Department of Physics, Tokyo Institute of Technology, Oh-okayama, Tokyo 152-8551, Japan*

³*Department of Physics, Osaka University, Toyonaka, Osaka 560-0043, Japan*

⁴*Department of Chemical and Materials Engineering, Arizona State University, Tempe, Arizona 85287-6006, USA*

⁵*Department of Applied Physics and Chemistry, University of Electro-Communications, Chofu, Tokyo 182-8585, Japan*
(February 2, 2008)

First-principles band calculations are performed for the first time for an open-structured zeolite (LTA) with guest atoms (potassium) introduced in their cages. A surprisingly simple band structure emerges, which indicates that this system may be regarded as a “supercrystal”, where each cluster of guest atoms with diameter $\sim 10\text{\AA}$ acts as a “superatom” with well-defined s - and p -like orbitals, which in turn form the bands around the Fermi energy. The calculated Coulomb and exchange energies for these states turn out to be in the strongly-correlated regime. With the dynamical mean-field theory we show the system should be on the Mott-insulator side, and, on a magnetic phase diagram for degenerate-orbital systems, around the ferromagnetic regime, in accord with experimental results. We envisage this class of systems can provide a new avenue for materials design.

PACS numbers: 82.75.Vx, 71.30.+h, 36.20.Kd

Materials design is usually done by varying chemical elements and/or atomic crystal structures. Here we consider doped zeolites, which are unique in that (i) they are host-guest systems, where the host itself appears in a rich variety (crystal structure of cages, size of the inter-cage window, etc), on top of rich possibilities for the species and the number of guest atoms [1]. (ii) the size of the cage is $\sim$ nanometer. We can note the distinction of the zeolites from the solid fullerene: The latter are also nanostructured supercrystals, but the relevant orbitals, even when doped with alkali metals, are LUMO/HOMO of the cage (buckeyball) rather than those of dopants [2]. While (i) implies higher degrees of freedom for the design, (ii) implies that the Coulomb interaction energy for the cluster doped in the cage, which only decreases inversely with the size, can remain large ($\sim$ eV for nanometer dimensions). Here we envisage that these can provide a fascinating playing ground for *systematically control* the electron correlation as a new avenue for materials design.

Indeed, experimental results by Nozue *et al* showed some zeolites (Fig.1) loaded with clusters ($\simeq$ five atoms per cage) of potassium is ferromagnetic for $T < 8\text{K}$ [3,4], which is unique in that magnetism occurs even though all the ingredients are non-magnetic elements [5]. At the same time, an infrared analysis for the K-loaded zeolite shows clear absorption edges, indicative of insulating behavior [6].

Here we address both phenomena, and show they can be explained in terms of strong electron correlations in a surprisingly simple electronic structure. We start by showing that the relevant states of K-doped zeolite can be viewed from a “supercrystal” point of view. Namely, the

single-particle electronic structure as computed within the local-density approximation (LDA) for a typical zeolite having a cubic array of cages is very accurately described as a tight-binding band of “superatoms” (i.e., the states in the clusters of dopants) with simple s and p orbitals. This explains why the optical spectrum can be interpreted as transitions between s and p (or p and d) orbitals in a simplified well [7]. For the LDA calculation we adopt the all-electron full-potential linear muffin-tin orbitals (FP-LMTO) [8]. In fact ours is the first reliable band structure calculation for zeolites [9].

Next we estimate the Coulomb and exchange interactions for these orbitals by plugging in the LDA wave functions, and show that the interactions are large compared with the single-particle bandwidth, indicating strong electron correlations. Last, we study the effect of correlations on the spectral function in the spirit of the LDA+dynamical mean-field theory [10], and show the system resides well on the Mott-insulator side. This resolves a puzzle that the band calculation predicts that the system is a metal, while experiments indicate an insulator; moreover we show the calculated exchange energy (Hund’s coupling in superatoms) indicates ferromagnetism in the multi-orbital magnetic phase diagram, in accord with experiments.

We start with the undoped zeolite with a typical structure having a simple-cubic array of cages (Fig.1), where each cage (called α) is an Archimedes polyhedron. The region surrounded by eight α cages forms another cage called β . Aluminosilicate with this structure (zeolite A) has Si and Al atoms situated at the vertices of the cages and connected by O atoms with the inner di-

ameter of α cage ~ 10 Å. The material used in most experiments [3,4] is K(potassium)-form zeolite A (abbreviated as LTA hereafter), whose chemical formula, $K_{12}Al_{12}Si_{12}O_{48}$ (with 84 atoms per unit cell), already contains some K atoms. Eleven out of the twelve K atoms are located on the centers of faces of the α cage (orange atoms in Fig.1), while the remaining K (red), assumed to be at the cage center, changes its position as K's are added to change the doping as we shall describe. For the atomic positions of Al, Si, O within the unit cell, we have adopted the accurate crystal structure obtained from a recent neutron powder diffraction study by Ikeda *et al* [11,12].

The result for the band structure for the undoped LTA is displayed in Fig.2, which shows that the undoped zeolite is an insulator with a gap $\simeq 4$ eV, where the wave functions indicate that, while the valence-top state sits on the framework, the conduction-band states (labeled as B-F) primarily reside within the α cage (for B,D,E,F) or within β (C).

The dispersion of the lowest conduction band (B) can be fitted, as shown in the right panel of Fig.2, by the dispersion of a tight-binding band on the simple cubic lattice, $\varepsilon(\mathbf{k}) = t_x \cos(k_x) + t_y \cos(k_y) + t_z \cos(k_z)$, with $(t_x, t_y, t_z) \simeq (-20, -10, -5)$ (meV). The fitting is excellent, and, with all of $t_x, t_y, t_z < 0$ and the wave function being nodeless (Fig.2(B), with its tetrahedral shape due to the configuration of surrounding K atoms), we may interpret the band as an “ s band” of the supercrystal. Similarly, three (D, E, F) out of the four next-lowest conduction bands, with large amplitudes within the α cage, may be interpreted as p bands.

Now we come to the doped case. When one K atom is doped per unit cell (denote as K_1LTA), the Fermi level shifts to the middle of the conduction (s) band (not shown), while the p band remains empty. Tight-binding fits to these bands are again excellent, with $(t_x, t_y, t_z) \simeq (-10, -10, -5)$ in meV for the s band and $\simeq (25, -10, -1)$ for the p . The good fit to the simple tight-binding model is highly nontrivial, since the framework, $(K^+)_{12}(Al^{3+})_{12}(Si^{4+})_{12}O^{2-}_{48}$ with nominal valence indicated, is an ionic compound. Chemically, the cage has a low electron affinity so that the electrons stay well away from the wall. This is reflected in the localization of the wave function, and provides an intuitive reason why a simple well is effectively realized.

If we further dope the system to have K_3LTA (which is experimentally in the magnetic regime), we have now four K atoms (the doped three on top of a red ball in Fig.1(b)), which form a cluster in the α cage. The precise atomic configuration has not been experimentally determined, so we have focused here on the configuration where the four atoms (at $(0.5 \pm x_1, 0.5 \pm x_1, 0.5)$) form a square, with $x_1 \simeq 0.25$ minimizing the total energy, although we have calculated for other possibilities such as a tetrahedral configuration.

If we look at the band structure and the wave functions for the K_3LTA in Fig.3, we can see that three bands around E_F (located above the s band that has fallen below E_F) have amplitudes within the α cage. We identify these as p_x, p_y , and p_z bands, respectively, as confirmed by a fit of the dispersions to the tight-binding model, where the fit is again excellent. To be precise E_F intersects the p_x and p_z bands, which are degenerate, reflecting the symmetry of the cluster. The fitted hopping integrals for s, p_x, p_y and p_z bands are, respectively, $(t_x, t_y, t_z) \simeq (-30.0, -25.0, -0.5), (125, -25.0, -62.5), (-12.5, 25.0, -50.0)$ and $(-12.5, -0.5, 75.0)$ in meV. The hopping integrals are almost an order of magnitude greater than those for K_1LTA , as expected from the larger cluster size. An ESR experiment shows that the g value decreases for K_nLTA with $n > 2$ [13]. This may be understood as the degeneracy of the p bands enhancing the spin-orbit interaction and reducing the g value.

Now we come to a big question of whether the system is strongly correlated. As mentioned, a puzzle is that experimentally K_1LTA and K_3LTA are insulators, while the LDA finds them to be metals. So we first estimate the Coulomb matrix elements. The largest one is the intra-orbital Coulomb interaction U , which is $U = \int |\phi_1(\mathbf{x})|^2 V(\mathbf{x} - \mathbf{y}) |\phi_1(\mathbf{y})|^2 d\mathbf{x} d\mathbf{y}$, where ϕ 's are the wave functions at Γ . Here V is assumed to be the bare Coulomb interaction as a first approximation, since the s and p wave functions are well localized in the interior of each cage [14]. U is calculated to be $U \simeq 4.5$ eV for the s band in K_1LTA , and $\simeq 4.0$ eV for the p_x band in K_3LTA . Given that $U/W \sim 10 \gg 1$, where W is the band width, we can expect that these materials are Mott insulators.

However, since the relevant bands are p bands with very anisotropic dispersions, we have to be careful in estimating the critical U_c for the metal-insulator transition. Here we have employed the dynamical mean-field theory [15] with the maximum entropy method [16] to estimate the transition point by calculating the spectral function in the single-band Hubbard model [17] for a typically anisotropic ($t_x : t_y : t_z = 5:1:1$) case as well as the isotropic (1:1:1) one.

Fig. 4 shows the spectra for various values of Hubbard U/W , where we can see that the system becomes an insulator (as identified from a gap in the spectral function) for U/W larger than $\simeq 2$ [18] in the anisotropic case. So we conclude that this particular K-doped zeolite is on the Mott-insulator side. In more general terms we expect that the metal-insulator transition can be controllable through control of U/W . For example, a zeolite called faujasite is known to be metallic when alkali-metal doped [19], where this form of zeolite has a significantly wider (7Å against 5Å for LTA) window between the cages, which should result in a smaller U/W .

We finally come to the magnetic property. To discuss this we require the inter-orbital U' and exchange integrals

J as well, where $U' = \int |\phi_1(\mathbf{x})|^2 V(\mathbf{x} - \mathbf{y}) |\phi_2(\mathbf{y})|^2 d\mathbf{x}d\mathbf{y}$, $J = \int \phi_1^\dagger(\mathbf{x}) \phi_2^\dagger(\mathbf{y}) V(\mathbf{x} - \mathbf{y}) \phi_1(\mathbf{y}) \phi_2(\mathbf{x}) d\mathbf{x}d\mathbf{y}$. For the p_x - p_z pair in K_3LTA , we find $U' \simeq 3.7$ eV, and $J \simeq 0.7$ eV, which are similar to those roughly estimated by Nozue *et al* [4]. Multi-orbital systems are in general favorable for ferromagnetism, since the inter-orbital kinetic-exchange coupling, $J_F^{\text{inter}} = -2t^2/(U' - J)$, is ferromagnetic (accompanied by an orbital superlattice structure). J_F^{inter} is estimated here to be (40 ~ 100) K for p_x and p_z bands in K_3LTA . This coupling competes with the intra-orbital kinetic-exchange coupling, $J_{AF}^{\text{intra}} \simeq 4Ut^2/(U^2 - J^2)$, which is antiferromagnetic. These exchange energies are (60 ~ 160) K for K_3LTA , which are two orders of magnitude greater than the exchange energy, $4t^2/U \simeq O(1)$ K, for the (single-band case of) K_1LTA , where the difference is mainly due to an order of magnitude difference in t . If we look at the magnetic phase diagram in the literature [20,21], K_3LTA is, as indicated in the inset of Fig.4, right around the ferromagnetic phase boundary.

Experimentally, ferromagnetism with finite magnetization has been observed for K_nLTA with $2 < n < 7$ [3,4], where the Curie temperature ~ 10 K for $n \simeq 3$ while the spin susceptibility for $T > 30$ K exhibits a Curie-Weiss law, $1/(T - \Theta)$, with the Weiss temperature $\Theta \simeq 0$ K for K_1LTA , while ($-40 \sim -30$) K for K_3LTA [3,4]. The doping dependence as well as the energy scale are consistent with the exchange interactions estimated here.

Finally we comment on the Mott transition, for which K_nLTA is experimentally [22] insulating even when the nominal doping level (averaged n) is fractional. This may possibly be related to a coexistence of differently doped regions with a domain structure [22,23]. It would be interesting to know whether superconductivity as in the high- T_c cuprates can appear when we realize doped Mott insulators in the present system (by, e.g., degrading such a domain structure). Future work should also include an elaboration of the LDF+DMFT approach. These will enable us to systematically study electronic and magnetic effects in the “supercrystal”, for which some experimental and theoretical attempts are under way.

This work was supported by a Grant-in-Aid for Scientific Research (A) Fund from the Ministry of Education, Culture, Sports, Science and Technology, Japan.

-
- [1] V. N. Bogomolov, Usp. Fiz. Nauk **124**, 171 (1978) [Sov. Phys. Usp. **21**, 77 (1978)].
 - [2] S. Saito and A. Oshiyama, Phys. Rev. Lett. **66**, 2637 (1991).
 - [3] Y. Nozue, T. Kodaira, and T. Goto, Phys. Rev. Lett. **68**, 3789 (1992).
 - [4] Y. Nozue, T. Kodaira, S. Ohwashi, T. Goto, and O.

- Terasaki, Phys. Rev. B **48**, 12253 (1993).
- [5] Ferromagnetism in materials having entirely non-magnetic elements has been experimentally reported for p -NPN [M. Takahashi *et al.*, Phys. Rev. Lett. **67**, 746 (1991) and for C_{60} -TDAE [P. M. Allemand *et al.*, Science **253**, 301 (1991)]. Theoretical proposals have been made for an atomic quantum wire [R. Arita *et al.*, Phys. Rev. B **57**, R6854 (1998)], and for a polymer [R. Arita *et al.*, Phys. Rev. Lett. **80**, 127202(2002)].
- [6] T. Nakano, Y. Ikemoto, and Y. Nozue, Eur. Phys. J. D **9**, 505 (1999).
- [7] T. Kodaira, Y. Nozue, S. Ohwashi, T. Goto, and O. Terasaki, Phys. Rev. B **48**, 12245 (1993).
- [8] M. Methfessel, M. van Schilfgaarde, and R.A. Casali in *Electronic Structure and Physical Properties of Solids*, edited by H. Dreyssé (Springer, Berlin, 2000), p.114.
- [9] Q. Sun, L. Ye, X. Xie [J. Appl. Phys. **84**, 3671 (1998)] have calculated the band structure of a fictitious Na-K mixed doped $Na_9K_3Si_{12}Al_{12}O_{48}$ (“lowly doped” in their terminology) or $Na_9K_{11}Si_{12}Al_{12}O_{48}$ (“highly doped”), but the former has in fact no alkali-metal doping, while the latter 8 K atoms doped, where Na cations are in either case accommodated in the β cage, an unlikely situation even when the mixed doping would be realized.
- [10] For review, see K. Held *et al.* in *Quantum Simulations of Complex Many-Body Systems: From Theory to Algorithms*, edited by J. Grotendorst, D. Marx and A. Muramatsu (Forschungszentrum Jülich, 2002), p.175.
- [11] T. Ikeda, T. Kodaira, F. Izumi, T. Kamiyama, and K. Ohsima, Chem. Phys. Lett. **318**, 93 (2000).
- [12] For the aluminosilicate an empirical (Lowenstein) rule [V. Gramlich and W.M. Meier, Z. Kristallogr. **133**, 134 (1971)] dictates that Si and Al be arranged alternately, but this makes the linear dimension of the unit cell doubled. In order to simplify the model, here we consider a unit cell that contains only one α (consequently one β) cage with a unit cell size of $a = 12.3$ Å. We have slightly shifted the position of the O atoms around the unit cell boundary to reconcile with the broken Lowenstein rule. We have confirmed this does not significantly change the band structure around E_F .
- [13] T. Nakano, Y. Ikemoto, and Y. Nozue, J. Mag. Mag. Mat., **226-230**, 238 (2001); J. Phys. Soc. Jpn. Suppl. **71**, 199 (2002).
- [14] The interaction parameters calculated by the Slater integrals can be overestimated, by > 1.3 for isolated ions and > 2 for solids, but the cluster in each cage here is closer to the former, and even if the factor is ~ 2 , this will not alter the present conclusion on the Mott-insulator and magnetic properties.
- [15] A. Georges, G. Kotliar, W. Krauth, and M. J. Rozenberg, Rev. Mod. Phys. **68**, 13 (1996).
- [16] M. Jarrell and J.E. Gubernatis, Phys. Rep. **269**, 135 (1996).
- [17] For orbitally degenerate systems, A. Koga, Y. Imai, N. Kawakami (cond-mat/0206064) and Y. Ono, M. Potthoff, R. Bulla (cond-mat/0206508) have shown that the critical U_c for the Mott transition increases with U' , decreases with J .
- [18] For an infinite-dimensional system the metal-insulator transition point has been estimated to be $U/W = 1 \sim 2$

- [15].
- [19] Y. Ikemoto, T. Nakano, M. Kuno, and Y. Nozue, *Physica B* **281-282**, 691 (2000).
- [20] K. Kusakabe and H. Aoki, *Physica B* **194-196**, 217 (1994).
- [21] T. Momoi and K. Kubo, *Phys. Rev. B* **58**, R567 (1998).
- [22] T. Nakano, Y. Ikemoto, and Y. Nozue, *Physica B* **281/282**, 688 (2000).
- [23] A super-structure in the array of clusters is experimentally detected for $n > 2$.




FIG. 1. Left: Geometry of the LTA structure. Right: Unit cell (i.e., α cage) of the undoped zeolite considered here, with dark blue: Si, light blue: Al, dark green: oxygen, orange and red: K.




FIG. 2. The band structure of the undoped zeolite LTA. The top right panel is a blowup of the lowest conduction band, where the red line is a tight-binding fit. Bottom panels are wave functions (red contours: positive, blue: negative) at Γ in the bands A-F as labeled in the band structure.




FIG. 3. Band structure of a K-doped zeolite K_3LTA . Colored curves are a tight-binding fit. Top left inset depicts the atomic configuration, where four red K's (the doped K + the red K in Fig.1) form a square in the α cage. Bottom panels are wave functions at Γ in the bands A-E as labeled in the band structure.




FIG. 4. Spectral function, $\rho(\omega)$, obtained with the dynamical mean-field theory for the Hubbard model on the cubic lattice with the isotropic(a) or an anisotropic(b) dispersions for various values of U/W . The bottom inset shows the magnetic phase diagram for the degenerate Hubbard model against the inter-orbital Coulomb (U') and the Hund coupling (J) interactions after Ref. [21], where the parameter region for the doped zeolite is indicated by blue hatch with its widths representing the dependence on the atomic configuration of the cluster and on the assumption of $U = U' + 2J$ on which the diagram is drawn. W is here defined as the width of the gaussian density of states.